

# TREX COMPANY TEST REPORT

**SCOPE OF WORK**

DYNAMIC WIND LOAD TESTING ON 8 FT WIDE BY 6 FT HIGH SECLUSIONS® FENCING

**REPORT NUMBER**

K4991.01-119-19-R0

**TEST DATES**

01/06/20 - 01/07/20

**ISSUE DATE**

02/11/20

**RECORD RETENTION END DATE**

01/07/24

**PAGES**


17

**DOCUMENT CONTROL NUMBER**

ATI 00648 (07/24/17)

RT-R-AMER-Test-2797

© 2017 INTERTEK





Total Quality. Assured.

130 Derry Court  
York, PA 17406

Telephone: 717-764-7700  
Facsimile: 717-764-4129  
www.intertek.com/building

## TEST REPORT FOR TREX COMPANY

Report No.: K4991.01-119-19-R0

Date: 02/11/20

### REPORT ISSUED TO TREX COMPANY, INC.

160 Exeter Drive  
Winchester, VA 22603

### SECTION 1 SCOPE

Intertek Building & Construction (B&C) was contracted by Trex Company to perform dynamic wind load testing on their 8 ft wide by 6 ft high Seclusions® wood-plastic composite privacy fence system. Results obtained are tested values and were secured by using the designated test method(s). Testing was conducted at Intertek B&C's test facility in York, PA.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory.

For INTERTEK B&C:

<b>COMPLETED BY:</b>	Robert G. Spayd
<b>TITLE:</b>	Technician II
<b>SIGNATURE:</b>	 <small>Digitally Signed by: Robert Spayd</small>
<b>DATE:</b>	02/11/20

RGS:tah/aas

<b>REVIEWED BY:</b>	Travis A. Hoover
<b>TITLE:</b>	Program Manager
<b>SIGNATURE:</b>	 <small>Digitally Signed by: Travis Hoover</small>
<b>DATE:</b>	02/11/20

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.



Total Quality. Assured.

130 Derry Court  
York, PA 17406

Telephone: 717-764-7700  
Facsimile: 717-764-4129  
[www.intertek.com/building](http://www.intertek.com/building)

## TEST REPORT FOR TREX COMPANY

Report No.: K4991.01-119-19-R0

Date: 02/11/20

### SECTION 2

#### MATERIAL SOURCE/INSTALLATION

Test samples were provided by the client. Test samples were inspected by a representative of Intertek B&C prior to testing. No compromising defects were observed. Representative samples of the test specimen(s) will be retained by Intertek B&C for a minimum of four years from the test completion date.

Test specimens were assembled by the client.

### SECTION 3

#### EQUIPMENT

Two propeller fan wind generators were utilized for testing. The propeller of each fan had a diameter of 84 in and was comprised of three/four Kevlar composite airfoil units belt-driven by a high-output V8 engine. Wind speed for each wind generator was calibrated according to AAMA 501.1-05. Deflections were measured with linear displacement transducers accurate to 0.01 in.

### SECTION 4

#### LIST OF OFFICIAL OBSERVERS

NAME	COMPANY
Glenn Muse	Trex Company
Ben Arthur	Trex Company
Sarah Price	Trex Company
Chris Scoville	Trex Company
Isaiah Gebhart	Intertek B&C
Scott T. Gladfelter	Intertek B&C
Kevin Eichelberger	Intertek B&C
Adam Schrum	Intertek B&C

**TEST REPORT FOR TREX COMPANY**

Report No.: K4991.01-119-19-R0

Date: 02/11/20

**SECTION 5****TEST PROCEDURE**

Three specimens (each consisting of a 2-panel/3-post fully assembled fence section) were tested. Each fence panel measured approximately 8 ft wide by 6 ft high. See drawings in Section 10 for detailed descriptions of assembly and components.

A steel test fixture was designed and fabricated to simulate a rigid post embedment. The bottom of the bottom rail was fixed at 3/8 in above the top of the test fixture. The wind generator outlet was located 4 ft from the face of the specimen and centered between the two panels. Linear transducers were fixed on the midspan of the top rail, middle of the infill area, and midspan of the bottom rail for deflection measurements. See drawings in Section 10 for detailed descriptions of assembly and components and photographs in Section 9 for specimen orientation with respect to wind direction.

Wind load testing began at 75 mph for all specimens and increased until failure or a maximum wind speed of 130 mph. Wind loads were performed with a relaxation period, following client-specified wind loads, to record permanent set measurements.

**SECTION 6****TEST CALCULATIONS****Wind Load Testing**

The duration of the applied wind load at each wind speed was determined by using the following equation:

$$t = 3600 / V_{fm} \quad (\text{Equation 1})$$

where:

$t$  = duration (s), required for a one mile long sample of air to pass

$V_{fm}$  = "fastest mile" wind speed (mph)

Wind speeds used in testing correlate with "fastest mile" wind speeds ( $V_{fm}$ ) for reference to codes and design standards. Maximum deflections were recorded at each load level.

**TEST REPORT FOR TREX COMPANY**

Report No.: K4991.01-119-19-R0

Date: 02/11/20

**SECTION 7**
**TEST SPECIMEN DESCRIPTIONS**

<b>SERIES/MODEL</b>	Seclusions® Privacy Fence
<b>DESCRIPTION</b>	8 ft wide by 6 ft high wood-plastic composite privacy fence
<b>TOP RAIL</b>	4 in wide by 4-3/4 in high by 1/2 in wall by 91 in long "T"-shaped wood-plastic composite extrusion with 1-7/16 in slot to accept pickets
<b>BOTTOM RAIL</b>	2-3/4 in wide by 5-1/8 in high by 0.08 in wall by 90-1/2 in long "H"-shaped 6063-T5 aluminum extrusion, which accepts two (2) 91 in long bottom rail covers to create bottom rail assembly, with 1-1/4 in slot to accept pickets
<b>PICKET/BOTTOM RAIL COVER</b>	5-3/4 in wide by 1 in deep by 1/4 in wall by 67 in long (picket) or 91 in long (bottom rail cover) "C"-shaped wood-plastic composite extrusion
<b>INFILL PANEL</b>	Nineteen (19) pickets (oriented vertically) per panel inserted into slots in top and bottom rails. First and last pickets attached to posts using three (3) #8 x 1-5/8 in self-starting wood screws at top/middle/bottom of each picket. Third-to-last picket at one end of panel secured to top and bottom rails on one side of panel using one (1) #8 x 1-5/8 in self-starting wood screw to maintain tightness of interlocking pickets.
<b>POST</b>	5 in square by 1/2 in wall by 108 in long hollow wood-plastic composite extrusion (30 in embedment)
<b>RAIL ATTACHMENT</b>	Four (4) nylon rail brackets per panel attached to posts using four (4) #8 x 1-5/8 in self-starting wood screws per bracket. Top rail attached to brackets using one (1) #8 x 1-5/8 in self-starting wood screw through top of rail at each end of rail.

## TEST REPORT FOR TREX COMPANY

Report No.: K4991.01-119-19-R0

Date: 02/11/20

### SECTION 8

#### TEST RESULTS

Seclusions® Privacy Fence

Test No. 1

Test Date: 01/06/20

WIND SPEED	DURATION	MAXIMUM DEFLECTION (in)					
		TOP		MID		BOTTOM	
		LEFT	RIGHT	LEFT	RIGHT	LEFT	RIGHT
75 mph	48 s	2.50	2.40	2.39	2.26	0.66	0.36
80 mph	45 s	2.96	2.91	2.50	2.93	0.74	0.44
Perm. Set	60 s	0.34	0.39	0.35	0.36	0.11	0.04
90 mph	40 s	3.71	3.13	3.40	3.39	0.86	0.52
100 mph	36 s	4.22	4.40	3.80	4.22	1.05	0.56
110 mph	33 s	5.21	5.49	4.81	5.15	1.13	0.65
115 mph	32 s	6.12	6.22	5.48	6.12	1.29	0.70
Perm. Set	60 s	1.08	1.09	1.01	0.98	0.24	0.09
120 mph	30 s	6.40	6.71	6.15	6.46	1.45	0.75
130 mph	28 s	8.40	8.31	7.50	7.82	1.56	0.72

**Observation:** At the end of the test, the last picket on the left panel of the fence assembly became disengaged from its attachment to the line post, but the infill panel remained intact while successfully sustaining 130 mph.

Maximum Sustained Wind Speed,  $V_{fm} = 130$  mph

Equivalent 3-second Gust Wind Speed,  $V_{3s, ASD} = (1.05 \times V_{fm}) + 10.5 = 147$  mph

Equivalent 3-second Gust Wind Speed,  $V_{3s, ULT} = (V_{3s, ASD} \div \sqrt{0.6}) = 190$  mph



**TEST REPORT FOR TREX COMPANY**

Report No.: K4991.01-119-19-R0

Date: 02/11/20

**TEST RESULTS (CONTINUED)**
**Test No. 2**
**Test Date: 01/06/20**

WIND SPEED	DURATION	MAXIMUM DEFLECTION (in)					
		TOP		MID		BOTTOM	
		LEFT	RIGHT	LEFT	RIGHT	LEFT	RIGHT
75 mph	48 s	2.45	2.38	2.24	2.01	0.84	0.34
80 mph	45 s	2.94	2.83	2.42	2.53	0.85	0.38
Perm. Set	60 s	0.43	0.43	0.38	0.38	0.17	0.08
90 mph	40 s	3.75	3.46	3.17	3.07	1.01	0.49
100 mph	36 s	4.46	4.31	3.70	3.82	1.13	0.53
115 mph	32 s	5.71	5.65	4.97	5.15	1.36	0.65
Perm. set	60 s	1.05	1.01	0.84	0.86	0.26	0.11
120 mph	30 s	6.21	6.25	5.26	5.64	1.42	0.69
130 mph	28 s	7.81	7.62	7.12	7.31	1.60	0.8

**Observation:** No visible damage at the completion of the test.

Maximum Sustained Wind Speed,  $V_{fm} = 130$  mph

Equivalent 3-second Gust Wind Speed,  $V_{3s, ASD} = (1.05 \times V_{fm}) + 10.5 = 147$  mph

Equivalent 3-second Gust Wind Speed,  $V_{3s, ULT} = (V_{3s, ASD} \div \sqrt{0.6}) = 190$  mph

## TEST REPORT FOR TREX COMPANY

Report No.: K4991.01-119-19-R0

Date: 02/11/20

### TEST RESULTS (CONTINUED)

Test No. 3

Test Date: 01/07/20

WIND SPEED	DURATION	MAXIMUM DEFLECTION (in)					
		TOP		MID		BOTTOM	
		LEFT	RIGHT	LEFT	RIGHT	LEFT	RIGHT
75 mph	48 s	2.06	2.03	1.71	1.81	0.57	0.34
80 mph	45 s	2.62	2.57	2.09	2.29	0.64	0.38
Perm. Set	60 s	0.20	0.19	0.15	0.16	0.03	0.03
90 mph	40 s	3.40	3.50	2.72	3.01	0.84	0.48
100 mph	36 s	4.32	4.13	3.34	3.70	0.92	0.57
115 mph	32 s	5.50	5.62	4.46	5.15	1.10	0.69
Perm. Set	60 s	0.73	0.72	0.53	0.61	0.08	0.07
120 mph	30 s	6.04	6.15	4.59	5.27	1.20	0.77
130 mph	28 s	7.85	7.90	5.12	7.04	1.32	0.72

**Observation:** No visible damage at the completion of the test.

Maximum Sustained Wind Speed,  $V_{fm} = 130$  mph

Equivalent 3-second Gust Wind Speed,  $V_{3s, ASD} = (1.05 \times V_{fm}) + 10.5 = 147$  mph

Equivalent 3-second Gust Wind Speed,  $V_{3s, ULT} = (V_{3s, ASD} \div \sqrt{0.6}) = 190$  mph




## TEST REPORT FOR TREX COMPANY

Report No.: K4991.01-119-19-R0

Date: 02/11/20

### SECTION 9

#### PHOTOGRAPHS




**Photo No. 1**

**Wind Generator Outlet Relative to Test Specimen  
Typical Dynamic Wind Load Setup**

**TEST REPORT FOR TREX COMPANY**

Report No.: K4991.01-119-19-R0

Date: 02/11/20



**Photo No. 2**

**Test No. 1 - Picket/Line Post Disengagement at Completion of 130 mph**


**SECTION 10**  
**DRAWINGS**

The component and assembly drawings that follow for the Seclusions® wood-plastic composite privacy fence system have been reviewed by Intertek B&C and are representative of the project reported herein. Project construction was verified by Intertek B&C per the drawings included in this report. Any deviations are documented herein or on the drawings.

# Trex® Seclusions®

## COMPOSITE FENCING SYSTEM

ARCHITECTURAL DRAWING:  
TREX SECLUSIONS FENCING  
6' TALL x 8' WIDE



COMPONENTS	QUANTITY	LENGTH
Post Cap: Pyramid, Flat, or Crown	1	
5" x 5" Post	1	108" *
4" x 4.9" Top Rail	1	91" *
1"x5.75" Interlocking Picket	19	67" *
1" x 5.75" Bottom Rail Cover	2	91" *
Aluminum Bottom Rail	1	90 1/2"
Fence Bracket	4	
1 5/8" (Typ) Exterior Wood Screws	24	

\* Length may vary

intertek


Test sample complies with these details.  
Deviations are noted.

Report # 1K4991-01

Date 1/3/20 Tech zy

### NOTES:

1. INSTALLATION TO BE COMPLETED PER MANUFACTURER'S SPECIFICATION.
2. THIS DRAWING IS PROVIDED FOR PLANNING PURPOSES. REFER TO MANUFACTURER'S INSTALLATIONS FOR CONSTRUCTION DETAILS.
3. REFER TO MANUFACTURER'S WEBSITE FOR PRODUCT INFORMATION.
4. DRAWING NOT TO SCALE.



Post Profile: Cut View / Elevation View

160 EXETER DR., WINCHESTER VA, 22603

WWW.TREXFENCING.COM

Trex®, the Trex® logo, and Trex Seclusions® are either federally registered trademarks, trademarks or trade dress of Trex Company, Inc., Winchester Virginia or its licensees. Copyright © 2019 RLA Designs. All rights reserved.



Total Quality. Assured.

130 Derry Court  
York, PA 17406

Telephone: 717-764-7700  
Facsimile: 717-764-4129  
[www.intertek.com/building](http://www.intertek.com/building)

## TEST REPORT FOR TREX COMPANY

Report No.: K4991.01-119-19-R0

Date: 02/11/20

### SECTION 11

#### REVISION LOG

REVISION #	DATE	PAGES	REVISION
0	02/11/20	N/A	Original Report Issue